

2023 Gleason Lake Dr & Carlson Pkwy Improvements Public Informational Meeting #1

November 8, 2021

Carlson Pkwy and 6th Ave Resurfacing/Rehabilitation Area



Presenters and Contacts

Nick Amatuccio, Project Engineer

- nickam@bolton-menk.com
- 612-965-3926

Mike Payne, Assistant City Engineer

- mpayne@plymouthmn.gov
- 763-509-5538

Mike Waltman, Project Manager


- mikewa@bolton-menk.com
- 952-890-0509






Topics in this Presentation

• Project team members will be available after the presentation for questions and discussion







Why does our street need rehabilitation?

Streets

- Aged and show signs of distress cracks, potholes, settlements
- Pavement Management Program started in 1987 with the goal of reducing roadway maintenance

Utilities

- Aging components on water valves
- Some deteriorating storm manholes

Traffic

Aged signal systems at Gleason and Cheshire with outdated components





Existing Pavement Conditions



Proposed Improvements

Street Reclaiming

- Mill off the top few inches of excess existing asphalt pavement and haul away
- Reclaim the remaining existing asphalt pavement and underlying aggregate base
 - Grind up into a recycled base material for the roadway
- Resurface the roadway over the reclaimed base material with new asphalt pavement
- Spot replacement of concrete curb and gutter on Carlson
 - Full replacement proposed on 6th Ave due to poor condition
- Match existing street widths
 - One possible exception 6th Ave
 - Full replacement on 6th Ave gives us the option to narrow the overly wide street
 - Doesn't appear to be a need for parking on 6th Ave, allowing for a narrowed street





Proposed Improvements Cont.

Utilities

- Storm sewer manhole and casting repairs
- Water valve repairs/maintenance
- Infiltration & inflow barriers on sanitary sewer manholes

Walks/Trails

- Pedestrian Ramp and sidewalk improvements at intersections
- Possible trail replacement along the north side of 6th Ave

Signals

System replacement/upgrades at Gleason and Cheshire





Construction Process

- 1. Remove pavement (milling and reclaiming of existing street pavement)
- 2. Utility repairs
- 3. Spot replacement of concrete curb and gutter
- 4. Signal replacements and upgrades
- 5. Roadway grading
- 6. First layer(s) of asphalt roadway is paved
- 7. Pour concrete pedestrian ramps and sidewalks
- 8. Pave asphalt trails
- 9. Restoration behind the curb (topsoil and turf)
- 10. Final lift of asphalt roadway is paved





Pavement Removals







Utility Repairs









Concrete Curb & Gutter Installation











Signals





Roadway Grading





Roadway Paving









Concrete Sidewalks Bolton-Menk.com



Asphalt Trails







Turf Restoration








Construction Impacts

Private Utilities (Gas, Power, Cable, Phone)

- May be relocated prior to and during construction
 - Residents should be notified of any planned outages by utility company
- Unplanned outages may occur during construction
 - Residents can report these outages directly to the utility company

Public Utilities (Water, Sewer)

- Planned water service shutdowns (several hours) minimal impacts in this area of the project
- No disruption to sewer service





Construction Restoration

Landscaping in right-of-way or easements – minimal impacts in this area of the project

- Trees, bushes, flowers, landscaping items, etc.
- May be removed due to rehabilitation of street or utilities
- Homeowner must remove/salvage items prior to construction if they wish to save the landscaping items
 - Project team can coordinate with residents on approximate disturbance limits as we near construction

Turf

Areas disturbed by construction activity will be seeded at the end of each construction phase

Irrigation Systems

Systems damaged by construction activity will be repaired

Driveways

- Driveways impacted by construction activity will be repaired
 - Asphalt saw cut and patch
 - Concrete removed at joint
 - Brick paver salvaged and reinstalled



Construction Access

Access During Construction


- One drivable lane for emergency services
 - Access will change as construction progresses
 - May be delays due to construction activity
- Carlson Pkwy and 6th Ave closed to thru traffic during major construction
 - Access for local residents and businesses only
 - Moving detour set up for Carlson Pkwy
- Direct access to driveway at end of the working day overnight and weekends if no work occurs
 - Exceptions concrete curb or driveway needs to cure for 7 days to allow access
 - Commercial properties will always have access through at least one driveway, even if it's half at a time
- Notify the project team of special needs or events
 - Wheelchair access and medical needs
 - Graduation parties
 - Weddings
 - Funerals



Carlson/494 **Detour**

Full Weekend Closure

- Accelerate majority of the work over one weekend
- Sunday work
- Possible night work







Construction Schedule

Typical Working Hours

Monday – Friday: 7 AM – Sunset

Saturday: 8 AM to 6 PM

Sunday and Holidays: No Work Allowed



Phased Construction Schedule

- Focus on constructing one area of the project before moving to the next area
- Prevent the Contractor from working on the entire project at once

Inconveniences and Delays will be common

The project team will help minimize these inconveniences to make things run as smooth as possible



Assessment Policy & Hearing

Special assessments applied to adjacent, benefiting properties

- 40% of street and storm sewer improvement costs is paid by the property owner
- City pays the remaining 60% of the street and storm costs

Project costs that are not assessed and fully paid by the City

- Watermain repairs
- Sanitary sewer repairs

Assessment Hearing

- Tentatively scheduled to occur at a City Council meeting in February 2023
- Notice of assessment and public hearing will be mailed two weeks prior to the Council meeting
 - · Notice will include exact amount of proposed special assessment to benefiting property



Assessment Payment Options

Option 1 – Pay in full or partial payment(s) by 10/31/23*

No interest applied

Option 2 – Pay in full between 11/1/23* and 11/15/24*

• Includes 1st year of interest

Option 3 – Pay over the assessment term with interest

- Paid through property taxes
- Option is selected by default if not paid in advance




^{*}Dates are tentative and subject to change

Project Website

City of Plymouth Project Website www.plymouthmn.gov/gleasonlake

- Project information, schedule, documents, updates, FAQ
- Sign up for email updates
 - Sent as needed leading up to construction
 - Sent at least once a week during construction





pedestrian ramps, as necessary, in accordance with the

Americans with Disabilities Act (ADA)

2021 Street





Project Schedule

Public Informational Meeting #1

November 8, 2021

Minnetonka will be holding an informational meeting in early December

60% Draft Plans

March 2022

Public Informational Meeting #2

Summer 2022

Final Plans Completed

Fall 2022

Council Meeting #1

November 2022

Present Feasibility Report & Plans

Bid Opening

December 2022 / January 2023

Public Informational Meeting #3

February 2023

Council Meeting #2

February 2023

Public Improvement & Assessment Hearing; Award Contract

Construction

April – November 2023





Next Steps

Meeting Feedback

- Collect feedback from residents
 - Comment Cards / Email / Phone Calls
- Residents and business owners may contact the project team to set up an individual meeting regarding your property

Coordination with Minnetonka Staff & Residents


- Set up individual meetings if requested
- City of Minnetonka public informational meeting (Tentative December 1st)



Thank You! Any Questions?

Nick Amatuccio, PE Project Engineer

Mike Payne, PE Assistant City Engineer





Real People. Real Solutions.

Bolton-Menk.com